



KEY

- Red line boundary
- External scope of works (SOW) boundary
- Crown spread of trees and vegetation to be removed for development
- Vegetation and tree removal
- Root protection area (RPA) as BS 5837:2012
- Existing Scrub
- Scrub to be removed
- Category A trees/groups retained
Trees of high quality with an estimated remaining life expectancy of at least 40 years
- Category B trees/groups retained
Trees of moderate quality with an estimated remaining life expectancy of at least 20 years
- Category C trees/groups retained
Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm
- Category U trees/groups
Trees in such condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years

1 = The tree identification number in as per the tree survey
Number prefixes:
T = An individual tree
G = A group of trees
H = A hedgeline formed by trees

NB - TO BE READ IN CONJUNCTION WITH THE TREE SURVEY AND AIA

NOTES:
SCALE: Do not scale from this drawing.
SETTING OUT: All setting out, levels, dimensions to be agreed on site. Do not use the information on this drawing without checking all dimensions on site. Any discrepancies between drawings, specifications and site works are to be reported to The Urbanists. Order of construction and setting out is to be agreed on site.
CHECK: This drawing must be the latest revision, read in conjunction with all other drawings, details, specifications and schedules. All dimensions are in millimetres unless otherwise stated. Where any contradiction or uncertainty arises between the drawings and/or the schedule of works / specification, it is the Contractor's responsibility to seek verification from The Urbanists before proceeding. No claims will be met by The Urbanists, where the Contractor continues work in absence of such confirmation.

No.	Date	By	Revision Notes
A	29/08/2025	LMC	Draft 1st issue
B	02/09/2025	FC	Removal of tree in SW SuDS basin

PROJECT STATUS:
S0 (WORK IN PROGRESS)

theurbanists

Client Trivallis

Project Penrhys

Title Phase 1A Vegetation Retention and Removal

Project ID Organiser Volume Level Type Role Desig Rev
2384 URB XX XX SK L 0003 B

Drawn CW **Date** 08/09/2025 **Checked** DS **Scale** 1:500 @ A1

The Urbanists (Cardiff) - Westgate House - 11 Worcester Street - CF10 1BR
The Urbanists (Bristol) - Generator Building - Finsbury Reach - BS1 6BX
T: 029 2023 6133 E: info@theurbanists.net W: www.theurbanists.net
© This drawing is copyright and may not be reproduced in whole or part without written authority.